



EXTERIOR FINISH SCHEDULE		
FINISH ID	DESCRIPTION	SPECIFICATIONS
MTL-1	PREFINISHED COPING	PRE-FINISHED COLOR: MATCH RAL#7021 MATTE MT0028 - "FLAT BLACK"
MTL-3	H.M. DOOR AND FRAME	COLOR: MATCH RAL#7021 MATTE MT0028 - "FLAT BLACK"
MTL-4	METAL CANOPY	POWDERCOAT COLOR: MATCH RAL#7021 MATTE MT0028 - "FLAT BLACK" UNDERSIDE OF CANOPIES TO VARY. COORDINATE FINAL FINISH SELECTIONS WITH ARCHITECT.
MTL-5	METAL DOWNSPOUT	COLOR: MATCH RAL#7021 MATTE MT0028 - "FLAT BLACK"
MTL-6	ROOF ACCESS LADDER	COLOR: MATCH RAL#7021 MATTE MT0028 - "FLAT BLACK"
SF-1	ANNODIZED STOREFRONT	COLOR: MATCH RAL#7021 MATTE MT0028 - "FLAT BLACK"
SP-3	STUCCO, FINE FINISH	CEMENT PLASTER SYSTEM COLOR: MATCH SW7504 KEYSTONE GRAY
SP-4	STUCCO, FINE FINISH	CEMENT PLASTER SYSTEM COLOR: MATCH SW7026 GRIFFIN
WD-5	FIBER CEMENT PANEL	NICHIHA VINTAGE WOOD COLOR: BARK; AWP 1818
SCRN-1	ROOFTOP EQUIPMENT SCREEN	PAINTED: P577 (SW7019)

GENERAL NOTES

- A. GENERAL CONTRACTOR TO COORDINATE AND SCHEDULE SIGNAGE INSTALLATION WITH THE SIGNAGE CONTRACTOR PROVIDING A MINIMUM SCHEDULING NOTICE OF 4 WEEKS AND 1 WEEK PRIOR TO SCHEDULED DATE OF INSTALLATION. CONSTRUCTION MANAGER TO PROVIDE GENERAL CONTRACTOR WITH SIGNAGE CONTRACTOR CONTACT INFORMATION.
- B. GENERAL CONTRACTOR SHALL COORDINATE ELECTRICAL CONTRACTOR TO FURNISH AND INSTALL ELECTRICAL CIRCUITS INCLUDING ALL CONDUIT, WIRE, CONNECTIONS AND BREAKER AT PANEL BOARD NECESSARY TO SERVE SIGNAGE.
- C. SIGNAGE CONTRACTOR TO INSTALL SIGNAGE IN COMPLIANCE WITH LOCAL CODES AND OBTAIN PERMIT.

KEYED NOTES

1. PRIMARY ENTRANCE DOOR(S)
2. SECONDARY (PATIO) ENTRANCE DOOR
3. PRE-FINISHED METAL COPING, TYPICAL
4. OUTLINE OF ROOF BEYOND
5. STORE ADDRESS: PROVIDE 3" HIGH BLACK ACRYLIC STORE ADDRESS ON GLAZING ABOVE MAIN ENTRY DOOR.
6. DT WINDOW SHELF: INSTALL SERVICE WINDOW SHELF AT 36" AFF INSIDE AND 42" AFF OUTSIDE, AS MEASURED ABOVE THE DT SURFACE.
7. PRE-FABRICATED METAL CANOPY INSTALLED BY GC. BASIS OF DESIGN: "SUPER LUMIDECK" BY MAPES ARCHITECTURAL CANOPIES. GC TO COORDINATE WITH CANOPY VENDOR.
8. CANOPY DOWNSPOUTS: CONNECT TO UNDERGROUND STORM DRAIN.
9. FUTURE SIGNAGE BY OTHERS (SHOWN FOR REFERENCE ONLY).
10. PROVIDE J-BOX WITH PULL STRING FOR FUTURE BUILDING SIGNAGE. COORDINATE LOCATION WITH SIGN VENDOR.
11. PROVIDE 3/4" MARINE GRADE PLYWOOD BLOCKING FOR EXTERIOR SIGNAGE. EXTEND BLOCKING 8" MINIMUM BEYOND EDGES OF SIGNAGE. COORDINATE EXTENTS W/ FUTURE SIGNAGE VENDOR.
12. EXTERIOR SCENCE LIGHTING
13. EXTERIOR EGRESS LIGHTING
14. PROVIDE RECESSED LIGHTING IN CANOPY. SEE ROOF PLAN.
15. CLEVIS AND TIE-ROD BY CANOPY MANUFACTURER INSTALLED BY CONTRACTOR.
16. CEMENT PLASTER CONTROL JOINT.
17. CONCRETE SILL BELOW STOREFRONT. SEE STRUCTURAL.

REV.	DATE	DESCRIPTION

WHITSETT
6405 BURLINGTON RD
WHITSETT, NC 27377

EXTERIOR ELEVATIONS

DATE	
PERMIT	--/------
BID	--/------
CONSTRUCTION	--/------
RECORD	--/------
DESIGNER	
PROJECT MANAGER	AK
DB	

JOB NO.
2020379.16

A2001